BRUHAT BANGALORE MAHANAGARA PALIKE
DASARAHALLI ZONE

Name of Work: Improvements and Construction of CC Roads at Kempegowda nagara 2nd & 3rd Main 4th 6th B & 6th C Cross & North side of the Ganesha Saw Mill road & Other Cross roads in Dasarahalli ward No:15

			Est. Cost Rs				40.00	Lakhs	
Sl	Description of Item	Unit	No	L	B	D	Qty	Rate	Amount
1	KSRB-2-2.2: **Earthwork excavation** for foundation of buildings, water supply, sanitary, lines and electrical conduits either in pits or in trenches 1.5 m and above in width, in hard soil not exceeding 1.5m. in depth including dressing the bottom and and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead up to 50 m. after breaking of clods complete as per specifications. Specification No. KBS 2.1(b) 2.3.5 Page No. 5/ Item No. 2.4/								
		Cum	1	90.00	1.10	0.75	74.25		
			1	15.00	1.10	0.75	12.38		
			1	10.00	1.05	0.75	7.88		
			2	33.00	0.90	0.30	17.82		
			1	48.00	0.90	0.30	12.96		
			2	25.00	0.90	0.30	13.50		
			1	45.00	0.90	0.30	12.15		
			1	110.00	0.90	0.30	29.70		
	Ammaji back Side 2nd c/s road		1	114.00	0.90	0.30	30.78		
							211.41	288.36	60962.00
	Basic Rate	267.00							
	Add Area Weightage 8%	21.36							
	Total	288.36							
2	Removing B.S.Slab of drain and stacking etc., complete Page No. 25/ Item No. 5.32/ PWD SR 2015-16								
		Sqm	1	90.00	1.20		108.00		
			1	15.00	1.20		18.00		
			1	10.00	1.00		10.00		
	Basic Rate	59.00					136.00	63.72	8666.00
	Add Area Weightage 8%	4.72							
	Total	63.72							
3	Refixing stone slabs of drains and pointing in CM 1:3 etc complete Page No. 25/ Item No.5.33/ PWD SR 2015-16								
		Sqm	Qty Vide Iteam No 2				136.00		
			60%				81.60	78.84	6433.00
	Basic Rate	73.00							
	Add Area Weightage 8%	5.84							
	Total	78.84							

Sl	Description of Item	Unit	No	L	B	D	Qty	Rate	Amount
4	KSRB 4-1.3: Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @180 kgs, with 40mm and down size graded granite metal coarse aggregates @0.8[illegible]cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2 (P.12/I.4.3) PWD - SR 2015-16)								
		Cum	1	90.00	1.10	0.15	14.850		
			1	15.00	1.10	0.15	2.475		
			1	10.00	1.05	0.15	1.575		
			2	33.00	0.90	0.15	8.910		
			1	48.00	0.90	0.15	6.480		
			2	25.00	0.90	0.15	6.750		
			1	45.00	0.90	0.15	6.075		
			1	110.00	0.90	0.15	14.850		
	Ammaji back Side 2nd c/s road		1	114.00	0.90	0.15	15.390		
	Basic Rate	4695.00					77.355	5070.60	392236.00
	Add Area Weightage 8%	375.60							
	Total	5070.60							
5	KSRRB M600-2. Cement Concrete Pavement :- Construction of un-reinforced, dowel jointed, plain cement concrete pavement over a prepared sub base with 43 grade cement design mix M30 at 360 kg per cum, with 25mm and down size graded granite metal coarse aggregate at 0.69 cum and fine aggregates @ 0.46 cum with superplastizer at 3lts conforming to IS 9103-1999 reaffirmed 2008. coarse and fine aggregate conforming to IS:383, mixed in a batching and mixing plant as per approved mix design, transported to site, laid with a fixed form or slip form paver, spread, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrane, sealant primer, joint sealant, debonding strip, dowel bar, tie rod, admixtures as approved, curing, compound, finishing to lines and grades as per drawing complete as per specifications.(Page No: 173, itNo: 22.2.1)								
			2	33.00	3.60	0.15	35.64		
			1	48.00	4.00	0.15	28.80		
			1	25.00	4.00	0.15	15.00		
			1	25.00	5.00	0.15	18.75		
			1	45.00	3.60	0.15	24.30		
			1	110.00	4.20	0.15	69.30		
			1	114.00	4.50	0.15	76.95		
			1	38.00	2.70	0.15	15.39		
							284.13	6943.32	1972806.00
	Basic Rate	6429.00							
	Add Area Weightage 8%	514.32							
	Total	6943.32							
6	KSRB-4-1.5 : Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 300kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69cum and fine aggregates @ 0.43cum, with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost all materials, labour, HOM of machinery, curing complete as per specifications.(Page No: 1, it:4.5)								
			1	90.00	0.90	0.10	8.10		
			1	15.00	0.90	0.10	1.35		
			1	10.00	0.75	0.10	0.75		

Sl	Description of Item	Unit	No	L	B	D	Qty	Rate	Amount
			2	90.00	0.15	0.90	24.30		
			2	15.00	0.15	0.90	4.05		
			2	10.00	0.15	0.90	2.70		
	Basic Rate	5548.00					41.250	5991.84	247163.00
	Add Area Weightage 8%	443.84							
	Total	5991.84							
7	KSRB 4-6.3: Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness above 200 mm including cost of all materials, labour complete as per specifications.(Page No: 15, itno: 4.30)								
		Sqm	2x2	90.00		0.90	324.00		
			2x2	15.00		0.90	54.00		
			2x2	10.00		0.90	36.00		
							414.00	403.92	167223.00
	Basic Rate	374.00							
	Add Area Weightage 8%	29.92							
	Total	403.92							
8	KSRB 4.9.2: Providing T.M.T. steel reinforcement for R.C.C. work including straightening cutting, bending, hooking, placing in position, lapping and (or welding wherever required, trying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.(Page-17, itNo: 4.46.3)								
		Kgs	1	284.130		35.00	9944.55		
			1	41.250		50.00	2062.50		
		Tonne					12007.05		
	Basic Rate	65287.00				Say	12.01	70509.96	846617.00
	Add Area Weightage 8%	5222.96							
	Total	70509.96							
9	Supplying and fixing precast rainforced concrete slab 10cm thick including cost of reinforcement as pwe design and drawing materials cost, tranportion hire charges of machinary, machine cutting the verticale face to get plain even surface ctc. Complete with all leads and lift convetyenc charges labour charges inclusive cost of all materials								
		Sqm	1	90.00	1.20		108.00		
			1	15.00	1.20		18.00		
			1	10.00	0.90		9.00		
		ADR					135.00	1600.00	216000.00
10	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading (Page 136 table) Page No. 133 Item No. 17.1 PWD SR 2015-16								
	Qnty vide itNo:1	Cum					211.41	78.24	16540.00
	Loding and unloding charges	62.20							
	Lead 4kms 2x1.28x4	10.24							
		72.44							
	Add Area Weightage 8%	5.80							
	Total	78.24							

Sl	Description of Item	Unit	No	L	B	D	Qty	Rate	Amount
11	QC & Other Charges								60000.00
12	Miscellaneous and UnforessenCharges								5354.00
								Total	4000000.00

(Rupees.Forty Lakhs Only)

CERTIFICATE:-

1 The Work spot has been inspected and the work is found to be necessary
2 The Estimate is prepared as per the PW,P & IWTD -SR-2015-16
3 The Provision made in estimate are adequate and essential.
4 This area comes under BBMP limits.

Assistant Engineer
Ward-15

Assistant Executive Engineer
T. Dasarahalli Sub-Division
B.B.M.P

Executive Engineer
Dasarahalli Division
B.B.M.P. Bangalore.

A/S

ನಂ. AC(DH) AS/4/16-17 ದಿನಾಂಕ : 12/05/2016

ರೂ. 40.00 Lakhs (Rupees Forty Lakhs only)

ಗಳ ಅಂದಾಜು ಪಟ್ಟಿಗೆ ಆಡಳಿತಾತ್ಮಕ ಮಂಜೂರಾತಿ ನೀಡಿದೆ

Page No. 41
Sl. No. 14

ಅಪರ ಆಯುಕ್ತರು
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ
ದಾಸರಹಳ್ಳಿ ವಲಯ, ಬೆಂಗಳೂರು

ನಂ. CE(D2)/TS/24/16-17 ದಿನಾಂಕ : 25/05/2016
PQ: 115

ರೂ. ~~40,000/-~~ Forty Lakhs) Rs 4000000/- (Rupees

ಗಳ ಅಂದಾಜು ಪಟ್ಟಿಗೆ ತಾಂತ್ರಿಕ ಮಂಜೂರಾತಿ ನೀಡಿದೆ.

ಮುಖ್ಯ ಅಭಿಯಂತರರು
ತಾಂತ್ರಿಕ ಸಹಾಯಕರು ಬಿ.ಬಿ.ಎಂ.ಪಿ.
ದಾಸರಹಳ್ಳಿ ವಲಯ, ಬೆಂಗಳೂರು.